

BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Name of Work: Construction of CC road at NMH Layout 5th Cross in Bagalagunte Ward No 14

Est. Cost Rs 15.00 Lakhs									
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 500-3: Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100mtr. sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications Specification No. KRBS 500-1 MORTH Chapter 5 Page No. 158/ Item No. 21.3/ PWD SR 2018-19								
		Sqm	1	139.00	4.00		556.00		
	Basic Rate	126.00					556.00	133.56	74259.00
	Add Area Weightage 6%	7.56							
	Total	133.56							
	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158, I No.20.18)								
		CUM	1	139.00	4.00	0.23	127.88		
							127.88	2001.28	255924.00
	Basic Rate	1888.00							
	Add Area Weightage 6%	113.28							
	Total	2001.28							
3	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.13/143) PWD - SR 2018-19)								
	22.18	Cum	1	139.00	4.00	0.15	83.40	5421.90	
							83.40	5408.12	451037.00
	Basic Rate	5102.00							
	Add Area Weightage 6%	306.12							
	Total	5408.12							

KSRRB M2200-5.9. Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height. (Pg.No.227, It.no.28.7.9)PWD - SR 2018-19)									
	Cum	1	139.00	4.00	0.15	83.40			
						83.40	5483.38	457314.00	
	Basic Rate	5173.00							
	Add Area Weightage 6%	310.38							
	Total	5483.38							
Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 136 Item No. 17.1 PWD SR 2016-17									
6	Loading and Unloading	57.00	Qty Vide Item No 01			580.00	73.99	42913.00	
	Lead 4 KMs 2x1.28x4	12.80							
		69.80							
	Add Area Weightage 6%	4.19							
	Total	73.99							
						Sub Total		1281447.00	
7	Tender Premium Charge 5%							64072.00	
8	GST Charge 12%							153774.00	
9	Miscellaneous and Unforeseen Charges							707.00	
							Total	1500000.00	
Rupees Fifteen Lakhs Only									

Assistant Engineer
Ward No 14

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P


Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ಪಂ.ಬೆ/ದಾ/ಸ/15/19-20
ದಿನಾಂಕ :
ರೂ. 15.00 Lakhs
Rupees Fifteen lakhs only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಧಾರಿತವಾಗಿ ನುಂಜೂರಿನಿಡಿದೆ
ಸಹಿ-
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ಪುರಂ, ಬೆಂಗಳೂರು.

ನಂ. ಬೆ/ದಾ/ಸ/50/18-19
ದಿನಾಂಕ : 30/01/19
ರೂ. 15.00 Lakhs only
(15.00) " "
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮೌಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ಪುರಂ, ಬೆಂಗಳೂರು

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bangalore.

Construction of ee Road in 5th cross NMH Layout Bagalagurte, Ward No. 14



Sketch showing NMH Layout 5th cross.

constructed area

PLAN NOT TO SCALE

[Signature]
 AC-

[Signature]
 ಮಂಡ್ಯ ಜಿಲ್ಲಾ ಪಂಚಾಯತ್
 ಮಂಡ್ಯ ಜಿಲ್ಲಾ ಪಂಚಾಯತ್
 ಮಂಡ್ಯ ಜಿಲ್ಲಾ ಪಂಚಾಯತ್
 ಮಂಡ್ಯ ಜಿಲ್ಲಾ ಪಂಚಾಯತ್